

# IMPERIAL ROOFING TILES

A SERIES OF  
SPECIFICATIONS AND DETAILS FOR  
ROOFING TILES

---

LUDOWICI-CELADON COMPANY

*Makers of IMPERIAL Roofing Tiles*

---

CHICAGO  
104 SOUTH MICHIGAN AVENUE

NEW YORK  
565 FIFTH AVENUE

WASHINGTON  
738 FIFTEENTH STREET, N. W.

ROOFING-TILES. CLAY. IMPERIAL  
LUDOWICI-CELADON COMPANY

A. I. A. FILE NUMBER 12-61



R

LU



# IMPERIAL ROOFING TILES

A SERIES OF  
SPECIFICATIONS AND DETAILS FOR  
ROOFING TILES

---

LUDOWICI-CELADON COMPANY

*Makers of IMPERIAL Roofing Tiles*

---

CHICAGO  
104 SOUTH MICHIGAN AVENUE

NEW YORK  
565 FIFTH AVENUE

WASHINGTON  
738 FIFTEENTH STREET, N. W.

ROOFING-TILES, CLAY, IMPERIAL  
LUDOWICI-CELADON COMPANY

A. I. A. FILE NUMBER 12-1



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Chimney Pots

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## CHIMNEY POTS

Chimney pots are made in various textures and colors especially adapted to use with our weathered effect tiles. They are also available in glazed colors for the modern treatment.



C.P.200



C.P.500, 510 and 520



C.P.600, 610, 620, 630, 640, 650 and 660



C.P.400, 410 and 420



C.P.300, 310 and 320

### SCHEDULE OF SIZES

NUMBER	FLUE	BASE	HEIGHT
C.P.200.....	7 1/2 "x7 1/2 "	13 "x13 "	15 "
C.P.300.....	8 " Dia.	14 "	18 "
C.P.310.....	12 " Dia.	18 "	21 "
C.P.320.....	15 " Dia.	21 "	25 "
C.P.400.....	8 " Dia.	14 1/2 "	25 "
C.P.410.....	12 " Dia.	18 1/2 "	29 "
C.P.420.....	15 " Dia.	21 "	32 "
C.P.500.....	8 " Dia.	14 "	15 "
C.P.510.....	12 " Dia.	18 "	18 "
C.P.520.....	15 " Dia.	21 "	22 "
C.P.600.....	10 " Dia.	13 "	15 "
C.P.610.....	12 " Dia.	15 "	18 "
C.P.620.....	15 " Dia.	18 "	20 "
C.P.630.....	18 " Dia.	21 1/2 "	23 "
C.P.640.....	23 " Dia.	26 "	30 "
*C.P.650.....	8 "x12 "	11 "x15 "	20 "
*C.P.660.....	12 "x17 "	15 "x20 "	30 "

\*Elliptical



# LUDOWICI-CELADON COMPANY

*Makers of IMPERIAL Roofing Tiles*

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## IMPERIAL ROOFING TILES

Produced since 1875.

Hard burned to afford enduring protection under the most severe weather conditions encountered.

Our nearest sales office will furnish samples or give information as to where displays or typical installations may be seen. Photographs of representative work on request.

Estimates promptly furnished from architect's plans and specifications.

Experienced service available for assistance in solving difficult roofing problems.

We are singularly well equipped to furnish tiles of quality. Our manufacture is carried on where the raw material is peculiarly adapted to the purpose; our plants are equipped with modern machinery; our research department develops methods for producing both modern and ancient effects at minimum cost. Large output and flexible production assure service on all operations.

Variety of product affords wide latitude in accomplishing pleasing roof effects.

Shingle tiles are produced in a variety of sizes, colors

and textures. Brittany Shingles may be so applied as faithfully to resemble ancient roofs of burned clay or stone, which are so interesting to the traveller in France and England. Crude Shingles are moulded duplicates of early original French tiles. Antique Shingles, more irregular, are ideal for the low rambling English design country house. Colonial Shingles, in texture and color, are remarkably like old split wood shingles. The Provincial Shingle, an inexpensive yet artistic pattern, is used in its dull-colored and weathered effects to subdue the roof, or in a range of brighter tones to give it accent. Yale Memorial tiles, as used on the Harkness Memorial Quadrangle at Yale University, on the New Duke University group, and other prominent buildings, especially lend themselves to the furthering of individual expression in a conservative manner.

Closed Shingle, English Shingle, French, Mission, Spanish, Roman and Greek tiles are offered in natural reds and fireflashed shades, or glazed in practically any color. They are also produced in various textures, including weathered surface effects.

### SHOW ROOMS

CHICAGO  
104 South Michigan Avenue

CINCINNATI  
622 Broadway

NEW YORK  
565 Fifth Avenue

BOSTON  
E. Stanley Wires Company  
120 South Boylston Street

WASHINGTON  
738 Fifteenth Street, N.W.

PHILADELPHIA  
1315 Walnut Street

### ARCHITECTURAL EXHIBITS

INDIANAPOLIS  
Architects Exhibit Building  
DETROIT  
Barlum Tower, Cadillac Square

ST. LOUIS  
Arcade Building  
CLEVELAND  
Hanna Building

NEW YORK  
101 Park Avenue  
BROOKLYN  
Brooklyn Daily Eagle Building

### INDEX

Pattern	Page	Pattern	Page
Chimney Pots	1	Garden Walk Edging	16
Shingle Tiles	3	Mission Tiles	17
Shingle Tiles	4	Mission Tiles	18
Shingle Tiles	5	Mission Tiles	19
Shingle Tiles	6	Mission Tiles	20
Shingle Tiles	7	Mission Tiles	21
Shingle Tiles	8	Mission Tiles	22
Interlocking Shingle Tiles	9	Spanish Tiles	23
Interlocking Shingle Tiles	10	Spanish Tiles	24
Interlocking Shingle Tiles	11	Spanish Tiles	25
Interlocking Shingle Tiles	12	Spanish Tiles	26
French Tiles	13	Roman and Greek Tiles	27
French Tiles	14	Roman and Greek Tiles	28
French Tiles	15	Roman and Greek Tiles	29
Tile Slabs and Tile Flagging	16	Floor Tiles	30

*If additional copies of this catalogue are desired, please write.*



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## SHINGLE TILES

These patterns are available in a range of colors in a variety of surface textures

### SPECIFICATIONS

*Note: Notes are explanatory or advisory only and should not be included in the specifications.*

*Note: Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.*

*Note: Clauses are selective. Include or omit as they apply.*



#### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (*specify pattern*) Shingle tiles and fittings of (*specify*) color.

(1b) (*Hips*) (*and*) (*valleys*) shall be cut before burning.

#### (2) Nails

All nails for flashings and tiles shall be copper.

#### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

#### (4) Wood Strips

(4a) Provide  $\frac{3}{4}$ " x 1" cant strips at eaves and 1" stringers of necessary height under (*hip rolls and*) ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

*Note: Include (4b) if roof base is concrete.*

#### (5) Flashings

(5a) At sides of vertical surfaces, insert base flashing between each course of tiles. Lap 3" and extend 4" under tiles and at least 6" up wall.

(5b) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5c) Masonry wall shall be cap flashed and pointed.

(5d) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5e) Extend gutter metal up roof to a point higher than outer edge of gutter.

(5f) **Open Valleys**—Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5g) **Closed Valleys**—Flash between each course of tiles with 16" strips of same length as tiles.

(5h) **Rounded Valleys**—Flash between each course of tiles with curved strips of same length as tiles. Extend strips 8" beyond the curve at either side of valley.

#### (6) Laying

(6a) Lay tiles (*regular*) (*irregular*) with (*specify*) average exposure and not less than 2" head lap on the third course. Double tiles at eave. Fasten with ( $1\frac{1}{2}$ " ( $1\frac{1}{4}$ " (*specify*) copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

*Note: Select whether regular or irregular and specify  $1\frac{1}{2}$ " nails for  $\frac{3}{8}$ " shingles;  $1\frac{1}{4}$ " nails for  $\frac{1}{2}$ " shingles; longer for thicker shingles.*

(6b) Leave opening of 6" or more across valleys.

(6c) Cement end bands in laps.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note: Include (6g) on circular roofs.*

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

*Note: Include (6h) on high buildings.*


Details concerning any roofing problem furnished on request.  
If additional copies of this catalogue are desired, please write.



## IMPERIAL SHINGLE TILES



PROVINCIAL	
Length.....	15 "
Width.....	7 "
Thickness.....	$\frac{1}{2}$ "
Average exposure.....	7" x $6\frac{1}{2}$ "
Average pieces per square.....	317
Average weight per square.....	1230 lbs.




BRITTANY	
Length.....	12 "
Width.....	7 "
Thickness.....	$\frac{5}{8}$ "
Average exposure.....	7" x 5 "
Average pieces per square.....	412
Average weight per square.....	1840 lbs.



## IMPERIAL SHINGLE TILES



ANTIQUE	
Length.....	12 "
Width.....	7 "
Thickness.....	$\frac{9}{16}$ "
Average exposure.....	7' x 5"
Average pieces per square.....	412
Average weight per square.....	1600 lbs.



CRUDE	
Length.....	12 "
Width.....	$6\frac{1}{4}$ "
Thickness.....	$\frac{5}{8}$ "
Average exposure.....	$6\frac{1}{4}$ ' x 5 "
Average pieces per square.....	460
Average weight per square.....	1850 lbs.

## IMPERIAL SHINGLE TILES

COLONIAL



## IMPERIAL SHINGLE TILES



Length.....	15"
Width.....	7 $\frac{3}{8}$ "
Thickness.....	$\frac{5}{8}$ "
Average exposure.....	7 $\frac{3}{8}$ " x 6 $\frac{1}{2}$ "
Average pieces per square.....	300
Average weight per square.....	1675 lbs.



## YALE MEMORIAL

Lengths.....	12", 14", 16"
Widths.....	6", 7", 8"
Thicknesses.....	$\frac{5}{8}$ ", $\frac{3}{4}$ ", 1"




IMPERIAL SHINGLE TILES



Brittany Shingle Tiles



Roll Ridge



Yale Memorial Tiles



Sprocket hip roll

3/8" Flat



1 2 3 4

Eyelet  
above for  
must show  
point dir  
a line w  
meets m  
Larger



# DETAILS OF IMPERIAL $\frac{3}{8}$ " FLAT AND $\frac{5}{8}$ " SLAB SHINGLE TILES AND FITTINGS

SCALE  $1\frac{1}{2}" = 1'-0"$


## IMPORTANT DATA

### $\frac{3}{8}$ " FLAT SHINGLE TILES


Length.....12"  
Width.....6"  
Average exposure.....6"x5"  
Average pieces per square.....480  
Average weight per square.1225 lbs.

### $\frac{5}{8}$ " SLAB SHINGLE TILES


Length.....12"  
Width.....6 $\frac{1}{4}"$   
Average exposure.....6 $\frac{1}{4}"$ x5"  
Average pieces per square.....461  
Average weight per square..1780 lbs.




$\frac{3}{8}$ " Flat Shingle Tile.




$\frac{5}{8}$ " Slab Shingle Tile.




Section A-A.



Section showing No. 203 ridge.




Hip section showing  
No. 111 Hip roll.




Cross section showing valley flashing  
on wood roof base. See specifications.

Siding corner




Elevation showing  $\frac{3}{8}$ "  
Flat Shingle Tiles.




Front

SCALE  $\frac{1}{4}" = 1'-0"$  for  
eyebrow detail only.



Side



Eave section showing gutter construction.

Eyebrow dormers must be constructed as shown above for  $\frac{5}{8}$ " Slab Shingle Tiles. Rafters and sheathing must show a straight line from the curved eave to the point directly above where it joins main roof and on a line with the point where center line of eyebrow meets main roof. See front elevation.

Larger or smaller effects can be secured providing

vertical height and radius shown are increased or decreased proportionately. Distance "A" should not be decreased and it must be increased when roof pitch is steeper than 12" rise in 12" run.

Crowd tiles at top of dormer and spread them at eave. Shorten exposure of tiles as they leave main roof until tail lines of tiles on both surfaces are aligned.



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles


CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue


WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## INTERLOCKING SHINGLE TILES



CLOSED SHINGLE



ENGLISH SHINGLE

These patterns are available in a range of colors in a variety of surface textures.

## SPECIFICATIONS

*Note:* Notes are explanatory or advisory only and should not be included in the specifications.

*Note:* Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.

*Note:* Clauses are selective. Include or omit as they apply.

### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (Closed) (English) Shingle tiles and fittings of (*specify*) color.

(1b) (*Hips*) (and) (*valleys*) shall be cut before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (and) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (and) 4" over (gutter) (and) (valley) metal.

### (4) Wood Strips

(4a) Provide  $\frac{3}{4}$ " x 1" cant strips at eaves.

*Note:* Include (4a) if English Shingles are specified.

(4b) Provide 1" stringers of necessary height under (*hip rolls* and) ridges.

(4c) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

*Note:* Include (4c) if roof base is concrete.

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 5" under tiles and turn up edge  $\frac{1}{4}$ ".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with 2" copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with 2" copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note:* Include (6g) on circular roofs.

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

*Note:* Include (6h) on high buildings.

Details concerning any roofing problem furnished on request.


If additional copies of this catalogue are desired, please write.



# DETAILS OF IMPERIAL INTERLOCKING SHINGLE TILES

## IMPORTANT DATA

CLOSED SHINGLE	
Length.....	11"
Width.....	8 3/4"
Average length exposure.....	8"
Average width exposure.....	8"
Average pieces per square.....	225
Average weight per square.....	900 lbs.
ENGLISH SHINGLE	
Length.....	13 1/4"
Width.....	8 1/4"
Average length exposure.....	10 1/8"
Average width exposure.....	7 1/4"
Average pieces per square.....	182
Average weight per square.....	900 lbs.



## HIP AND RIDGE STRINGER HEIGHTS

ROOF PITCH	CLOSED SHINGLE		ENGLISH SHINGLE	
	HIP No. 118	HIP No. 120	HIP No. 211	RIDGE No. 211
4" Rise to 12" Run.....	2 1/2"	3 1/4"	3 1/4"	3"
5" Rise to 12" Run.....	2 7/8"	3 3/4"	3 3/4"	2 3/4"
6" Rise to 12" Run.....	3 1/8"	4"	4"	2 3/4"
7" Rise to 12" Run.....	3 3/8"	4 1/4"	4 1/4"	2 3/4"
8" Rise to 12" Run.....	3 5/8"	4 1/2"	4 1/2"	2"
9" Rise to 12" Run.....	4 1/8"	4 3/4"	4 3/4"	1 3/4"
10" Rise to 12" Run.....	4 3/8"	5"	5"	1 1/2"
11" Rise to 12" Run.....	4 5/8"	5 1/4"	5 1/4"	1 1/2"
12" Rise to 12" Run.....	5 1/8"	5 1/2"	5 1/2"	1"
13" Rise to 12" Run.....	5 3/8"	5 3/4"	5 3/4"	1"
14" Rise to 12" Run.....	5 5/8"	5 3/4"	5 3/4"	1"

## CORRECT RAFTER LENGTHS FOR FULL LENGTH TILES


Based on 2" projection at eave of roof.

COURSE	CLOSED SHINGLE	ENGLISH SHINGLE
1.....	9"	11 1/4"
2.....	17"	21"
3.....	25"	31 1/2"
4.....	33"	41 1/2"
5.....	41"	51 1/2"
6.....	49"	61 1/2"
7.....	57"	72"
8.....	65"	82 1/2"
9.....	73"	92 1/2"
10.....	81"	102 1/2"
11.....	89"	112 1/2"




# DETAILS OF IMPERIAL INTERLOCKING SHINGLE TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Deck section showing  
No. 211 ridge.




Section showing flashing  
under side of tiles.




Deck section showing  
No. 211 deck  
mould-raised flange.




Deck section showing  
No. 211 cut-off  
ridge.




Deck section showing  
flashing over top  
of tiles.



Section showing flashing  
under  $\frac{3}{8}"$  Flat Shingle Tiles.




Section showing gutter  
construction for English  
Shingle Tiles.




Hip section showing No. 118  
hip roll used with Closed  
Shingle Tiles.




Section showing right gable  
rake and end band.




Section showing sunken gutter treatment.  
NOTE: When English Shingle Tiles are used, under eaves are  
omitted and distance below gutter is  $11\frac{1}{4}"$ .



Section showing flashing  
over top of tiles.



Cut hip—Left.




Cut valley—Right.




# DETAILS OF IMPERIAL INTERLOCKING SHINGLE TILES AND FITTINGS


APPLICATION OVER CONCRETE

SCALE  $1\frac{1}{2}" = 1'-0"$ 

Section showing valley flashing on concrete roof base.




Longitudinal section through roof.




Cross section through roof.

Application of wood strips to concrete roof base.  
Exact spacing of horizontal strips determined by shade of tiles.


## DIAGRAM OF EYEBROW DORMERS

SCALE  $\frac{1}{4}" = 1'-0"$ 


Front



Front



Side



Side

Eyebrow dormers must be constructed as shown above for Closed Shingle Tiles. Rafters and sheathing must show a straight line from the curved eave to the point directly above where it joins main roof and on a line with the point where center line of eyebrow meets main roof. See front elevation.

Larger or smaller effects can be secured providing

vertical height and radii shown are increased or decreased proportionately. Distance "A" should not be decreased and it must be increased when roof pitch is steeper than 12" rise in 12" run.

NOTE: For English Shingle tiles, eyebrow width and distance "A" must be increased 2'-0". The height remains the same.



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## FRENCH TILES

This pattern is available in a range of colors

## SPECIFICATIONS

*Note: Notes are explanatory or advisory only and should not be included in the specifications.*

*Note: Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.*

*Note: Clauses are selective. Include or omit as they apply.*



### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's *Imperial French* tiles and fittings of (*specify*) color.

(1b) (*Hips*) (*and*) (*valleys*) shall be cut before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" *up* vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

### (4) Wood Strips

(4a) Provide  $1\frac{1}{2}$ " x 2" cant strips at eaves and 1" stringers of necessary height under (*hip rolls and*) ridges.

(4b) Embed parallel with the pitch on 20" centers  $1\frac{1}{2}$ " x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install  $1\frac{1}{2}$ " x 2" strips spaced to suit tiles.

*Note: Include (4b) if roof base is concrete.*

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 5" under tiles and turn up edge  $\frac{1}{4}$ ".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with  $2\frac{1}{2}$ " copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with 2" copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note: Include (6g) on circular roofs.*

(6h) Cement all tiles in laps, using 40 lbs. of elastic cement per square.

(6i) Copper clamp shall be placed in side lock of each tile at point directly above head of tile below. Nail clamp to roof base.


*Note: Include either (6h) or (6i) on high buildings.*

Details concerning any roofing problem furnished on request.  
If additional copies of this catalogue are desired, please write.



## DETAILS OF IMPERIAL FRENCH TILES

IMPORTANT DATA	
Length.....	16 $\frac{1}{4}$ "
Width.....	9"
Average length exposure.....	13 $\frac{3}{8}$ "
Average width exposure.....	8 $\frac{5}{8}$ "
Average pieces per square.....	133
Average weight per square.....	935 lbs.

CORRECT RAFTER LENGTHS  
FOR FULL LENGTH TILES

Based on 2" projection at eave of roof.

COURSE	RAFTER
1.....	14"
2.....	27 $\frac{1}{2}$ "
3.....	40 $\frac{1}{2}$ "
4.....	54"
5.....	67 $\frac{1}{2}$ "
6.....	80 $\frac{1}{2}$ "
7.....	94 $\frac{1}{2}$ "
8.....	107 $\frac{1}{2}$ "
9.....	121"
10.....	134 $\frac{1}{2}$ "


## HIP AND RIDGE STRINGER HEIGHTS

ROOF PITCH	HIP NO. 102	RIDGE NO. 206
4" Rise to 12" Run.....	4"	5 $\frac{1}{4}$ "
5" Rise to 12" Run.....	4"	5"
6" Rise to 12" Run.....	4"	4 $\frac{3}{4}$ "
7" Rise to 12" Run.....	4"	4 $\frac{1}{2}$ "
8" Rise to 12" Run.....	4"	4 $\frac{1}{4}$ "
9" Rise to 12" Run.....	4"	4"
10" Rise to 12" Run.....	4"	3 $\frac{3}{4}$ "
11" Rise to 12" Run.....	4"	3 $\frac{1}{2}$ "
12" Rise to 12" Run.....	4"	3 $\frac{1}{4}$ "
13" Rise to 12" Run.....	4"	3"
14" Rise to 12" Run.....	4"	2 $\frac{3}{4}$ "
15" Rise to 12" Run.....	4"	2 $\frac{1}{2}$ "




# DETAILS OF IMPERIAL FRENCH TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$



Cut hip—Left.




Section showing flashing under side of tiles.




Deck section showing No. 206 deck mould-raised flange.




Section showing right gable rake.




Section showing valley flashing on concrete roof base.




Longitudinal section through roof. Application of wood strips to concrete roof base. Exact spacing of horizontal strips determined by shade of tiles.




Section showing sunken gutter treatment.




Hip section showing No. 102 hip roll.




Deck section showing No. 206 ridge.



Deck section showing No. 206 cut-off ridge.




Section showing flashing under  $\frac{3}{8}"$  Flat Shingle Tiles.



Section showing flashing over top of tiles.



Cross section through roof.



Cut valley—Right.



# LUDOWICI-CELADON COMPANY

*Makers of IMPERIAL Roofing Tiles*


CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

*Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS*

## TILE SLABS



In addition to shale red colors, tile slabs are manufactured in a range of browns and fire-flashed shades. A complete line of tile slab fittings is available.

### NUMBER OF PIECES PER SQUARE

Mortar Joint	6"x6"x1"	6"x9"x1"	9"x9"x1"
1/2"	384	258	173
3/4"	369	250	168
1"	355	241	164
1 1/4"	341	234	160



6"x9"x1"



6"x6"x1"




## GARDEN WALK EDGING

Made in red, fire-flashed and black. Placed in the ground along walks or driveways it makes an interesting and practical edging for lawns or flower borders.

## TILE FLAGGING

Made in a variety of colors. The texture suggests that of old stone flagging. Size approximately 9"x12"x1 1/4".





# LUDOWICI-CELADON COMPANY

Makers of *IMPERIAL Roofing Tiles*

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## MISSION TILES

These patterns are available in a range of colors in a variety of surface textures

### SPECIFICATIONS

*Note:* Notes are explanatory or advisory only and should not be included in the specifications.

*Note:* Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.

*Note:* Clauses are selective. Include or omit as they apply.



#### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (*specify pattern*) Mission Tiles and fittings of (*specify*) color.

(1b) Covers shall be used as (*hip roll and*) ridge.

(1c) (*Hips shall be cut*) (*and*) valleys shall be cut and closed before burning.

#### (2) Nails

All nails for flashings and tiles shall be copper.

#### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

#### (4) Wood Strips

(4a) Provide 1" strips of necessary height under covers (*hip rolls*) and ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit pan tiles.

*Note:* Include (4b) if roof base is concrete.

#### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 4" under tiles and turn up edge 2".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

#### (6) Laying

(6a) Lay tiles (*regular*) (*irregular*) exposure with not less than 3" lap. Fasten with 2" copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) **Irregular Effect**—Lay pans at actual exposure. Vary exposures of covers to avoid horizontal and diagonal lines using 10% additional covers.

(6c) Leave opening of 6" or more across valleys.

(6d) Cement gable rakes to field tiles and fasten with  $2\frac{1}{2}$ " copper nails.

(6e) Cement (*hip rolls*) (*and*) (*ridges*) in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note:* Include (6g) on circular roofs.


(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

*Note:* Include (6h) on high buildings.


Details concerning any roofing problem furnished on request.  
If additional copies of this catalogue are desired, please write.




# DETAILS OF IMPERIAL STRAIGHT BARREL MISSION TILES AND FITTINGS



Section showing split cover gable rake also flashing under side of tiles.



Section showing cover over concealed gutter.  
Pan is omitted.




IMPORTANT DATA

Length.....	14 1/4"	18"
Width center to center of covers.....	11 1/2"	11 1/2"
Average length exposure.....	11 1/4"	15"
Average pieces per square.....	224	170
Average weight per square.....	1250 lbs.	1250 lbs.


SCALE 1 1/2" = 1'-0"




# DETAILS OF IMPERIAL 18" CUBANA TAPERED MISSION TILES AND FITTINGS



Section showing split cover gable rake.



Section showing cover over concealed gutter. Pan is omitted.



## IMPORTANT DATA

Length, pan . . . . .	18 "
Length, cover . . . . .	18 "
Width center to center of covers . . . . .	11 1/4 "
Average length exposure, pans . . . . .	15 "
Average length exposure, covers . . . . .	15 "
Average pieces per square, pans . . . . .	85
Average weight per square, covers . . . . .	1265 lbs.

Note: 18" Straight Barrel pans furnished with this pattern.

SCALE 1 1/2" = 1'-0"

# DETAILS OF IMPERIAL LARGE TAPERED MISSION TILES AND FITTINGS

IMPORTANT DATA



# DETAILS OF IMPERIAL LARGE TAPERED MISSION TILES AND FITTINGS

## IMPORTANT DATA


### LARGE TAPERED PANS AND COVERS

Length.....	16 3/4"
Width center to center of covers.....	10 1/4"
Average length exposure.....	13 3/4"
Average pieces per square.....	200
Average weight per square.....	1600 lbs.

### LARGE TAPERED COVERS AND 18" STRAIGHT BARREL PANS

Length, pan.....	18"
Length, cover.....	16 3/4"
Width center to center of covers.....	11"
Average length exposure, pans.....	15"
Average length exposure, covers.....	13 3/4"
Average pieces per square, pans.....	87
Average pieces per square, covers.....	95
Average weight per square.....	1400 lbs.

SCALE 1 1/2" = 1'-0"




Section showing cover over concealed gutter. Pan is omitted.


NOTE: When 18" Straight Barrel pans are used, distance below gutter should be 16".




Large Tapered pans and covers.



Section showing Large Tapered pans and covers, also split cover gable rake.



Section showing Large Tapered covers with 18" Straight Barrel pans, also split cover gable rake.



Large Tapered covers and Straight Barrel pans.




# DETAILS OF IMPERIAL SMALL TAPERED MISSION TILES AND FITTINGS

## IMPORTANT DATA SMALL TAPERED PANS AND COVERS


Length .....	14 1/4"
Width center to center of covers .....	9 5/8"
Average length exposure .....	11 1/4"
Average pieces per square .....	270
Average weight per square .....	1380 lbs.

SMALL TAPERED COVERS AND 14 1/4" STRAIGHT BARREL PANS	
Length, pan .....	14 1/4"
Length, cover .....	14 1/4"
Width center to center of covers .....	10 1/8"
Average length exposure, pans .....	11 1/4"
Average length exposure, covers .....	11 1/4"
Average pieces per square, pans .....	128
Average pieces per square, covers .....	128
Average weight per square .....	1350 lbs.


Section showing cover over concealed gutter. Pan is omitted.




SCALE 1 1/2" = 1'-0"




Small Tapered pans and covers.



Section showing Small Tapered pans and covers, also split cover gable rake.



Section showing Small Tapered covers with 14 1/4" Straight Barrel pans, also split cover gable rake.



Small Tapered covers and Straight Barrel pans.








# DETAILS OF IMPERIAL 18" TAPERED MISSION TILES AND FITTINGS

## IMPORTANT DATA

18" TAPERED PANS AND COVERS	
Length.....	18"
Width center to center of covers.....	9½"
Average length exposure.....	15"
Average pieces per square.....	204
Average weight per square.....	1600 lbs.

18" TAPERED COVERS AND 18" STRAIGHT BARREL PANS	
Length, pan.....	18"
Length, cover.....	18"
Width center to center of covers.....	10"
Average length exposure, pans.....	15"
Average length exposure, covers.....	15"
Average pieces per square, pans.....	96
Average pieces per square, covers.....	96
Average weight per square.....	1350 lbs.

SCALE 1½" = 1'-0"





# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## SPANISH TILES

This pattern is available in a range of colors in a variety of surface textures

## SPECIFICATIONS

*Note: Notes are explanatory or advisory only and should not be included in the specifications.*

*Note: Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.*

*Note: Clauses are selective. Include or omit as they apply.*



### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial Spanish tiles and fittings of (*specify*) color.

(1b) (*Hips shall be cut*) (*and*) valleys shall be cut and closed before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" *up vertical walls*) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

### (4) Wood Strips

(4a) Provide 1" x 2" strips under end bands and 1" stringers of necessary height under (*hip rolls and*) ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

*Note: Include (4b) if roof base is concrete.*

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{2}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 4" under tiles and turn up edge  $1\frac{1}{2}$ ".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with  $1\frac{1}{2}$ " copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with  $2\frac{1}{2}$ " copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note: Include (6g) on circular roofs.*


(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

*Note: Include (6h) on high buildings.*

Details concerning any roofing problem furnished on request.  
If additional copies of this catalogue are desired, please write.



## DETAILS OF IMPERIAL SPANISH TILES

CORRECT RAFTER LENGTHS FOR  
FULL LENGTH TILES

Based on 2" projection at eave of roof.

COURSE	RAFTER
1.....	11 1/2"
2.....	21 1/2"
3.....	31 1/2"
4.....	42 1/2"
5.....	52 1/2"
6.....	62 1/2"
7.....	72 1/2"
8.....	83 1/2"
9.....	93 1/2"
10.....	103 1/2"
11.....	113 1/2"


## HIP AND RIDGE STRINGER HEIGHTS

ROOF PITCH	HIP NO. 102	RIDGE NO. 206
4" Rise to 12" Run.....	5"	6 1/2"
5" Rise to 12" Run.....	5"	6 1/2"
6" Rise to 12" Run.....	5"	6"
7" Rise to 12" Run.....	5"	5 3/4"
8" Rise to 12" Run.....	5"	5 1/2"
9" Rise to 12" Run.....	5"	5 1/4"
10" Rise to 12" Run.....	5"	5 1/4"
11" Rise to 12" Run.....	5"	5 1/4"
12" Rise to 12" Run.....	5"	5"
13" Rise to 12" Run.....	4 3/4"	4 3/4"
14" Rise to 12" Run.....	4 3/4"	4 3/4"
15" Rise to 12" Run.....	4 3/4"	4 3/4"




# DETAILS OF IMPERIAL SPANISH TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Deck section showing  
flashing over top  
of tiles.




Hip section showing  
No. 102 hip roll.




Deck section showing No. 206  
cut-off ridge and 3" x 4" scuppers  
draining deck.




Section showing flashing  
under  $\frac{3}{8}"$  Flat Shingle Tiles.



Deck section showing  
No. 206 deck  
mould-raised flange.




Deck section showing  
No. 206 ridge.




Section showing end  
band over concealed gutter.



Section showing left  
gable rake and end band.



Section showing flashing  
under side of tiles.




Section showing flashing  
over top of tiles.




## DETAILS OF IMPERIAL SPANISH TILES AND FITTINGS

## APPLICATION OVER CONCRETE



Application of wood strips to concrete roof base.  
Exact spacing of horizontal strips determined by shade of tiles.

## DIAGRAM OF EYEBROW DORMERS

SCALE  $\frac{1}{4}" = 1'-0"$ 

Eyebrow dormers must be constructed as shown above for Spanish tiles. Rafters and sheathing must show a straight line from the curved eave to the point directly above where it joins main roof and on a line with the point where center line of eyebrow meets main roof. See front elevation.

Larger or smaller effects can be secured providing vertical height and radii shown are increased or decreased proportionately.

Distance "A" should not be decreased and it must be increased when roof pitch is steeper than 12" rise in 12" run.



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles


CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.


Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## ROMAN TILES



These patterns are available in a range of colors in a variety of surface textures.

## GREEK TILES



## SPECIFICATIONS

*Note: Notes are explanatory or advisory only and should not be included in the specifications.*

*Note: Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.*

*Note: Clauses are selective. Include or omit as they apply.*

### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (*Roman*) (*Greek*) tiles and fittings of (*specify*) color.

(1b) (*Hips shall be cut*) (*and*) valleys shall be cut and closed before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" *up vertical walls*) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

### (4) Wood Strips

(4a) Provide 1" x  $2\frac{1}{2}$ " strips under covers and 1" stringers of necessary height under (*hip rolls and*) ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit pan tiles.

*Note: Include (4b) if roof base is concrete.*

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 4" under tiles and turn up edge 2".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with  $1\frac{1}{2}$ " copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with  $2\frac{1}{2}$ " copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note: Include (6g) on circular roofs.*

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

*Note: Include (6h) on high buildings.*

Details concerning any roofing problem furnished on request.  
If additional copies of this catalogue are desired, please write.




## DETAILS OF IMPERIAL ROMAN AND GREEK TILES

## IMPORTANT DATA

ROMAN	
Length.....	12 $\frac{3}{4}$ "
Width center to center of covers.....	12"
Average length exposure.....	10"
Average pieces per square.....	240
Average weight per square.....	1100 lbs.

GREEK	
Length.....	12 $\frac{3}{4}$ "
Width center to center of covers.....	12"
Average length exposure.....	10"
Average pieces per square.....	240
Average weight per square.....	1250 lbs.

CORRECT RAFTER LENGTHS  
FOR FULL LENGTH ROMAN  
OR GREEK TILES

Based on 2" projection at eave of roof.

COURSE	RAFTER
1.....	10 $\frac{3}{4}$ "
2.....	20 $\frac{3}{4}$ "
3.....	30 $\frac{3}{4}$ "
4.....	40 $\frac{3}{4}$ "
5.....	50 $\frac{3}{4}$ "
6.....	60 $\frac{3}{4}$ "
7.....	70 $\frac{3}{4}$ "
8.....	80 $\frac{3}{4}$ "
9.....	90 $\frac{3}{4}$ "
10.....	100 $\frac{3}{4}$ "
11.....	110 $\frac{3}{4}$ "


## HIP AND RIDGE STRINGER HEIGHTS

Roof Pitch	ROMAN		GREEK	
	Hip No. 102	Ridge No. 206	Hip-Cover	Ridge No. 211
4" Rise to 12" Run.....	6 $\frac{3}{4}$ "	7 $\frac{1}{4}$ "	7"	6"
5" Rise to 12" Run.....	6 $\frac{1}{4}$ "	7"	7"	5 $\frac{3}{4}$ "
6" Rise to 12" Run.....	6 $\frac{1}{4}$ "	6 $\frac{3}{4}$ "	7"	5 $\frac{3}{4}$ "
7" Rise to 12" Run.....	6 $\frac{1}{4}$ "	6 $\frac{1}{4}$ "	7"	5 $\frac{3}{4}$ "
8" Rise to 12" Run.....	6 $\frac{1}{4}$ "	6 $\frac{1}{4}$ "	6 $\frac{3}{4}$ "	5 $\frac{3}{4}$ "
9" Rise to 12" Run.....	6 $\frac{1}{4}$ "	6 $\frac{1}{4}$ "	6 $\frac{3}{4}$ "	5"
10" Rise to 12" Run.....	6 $\frac{1}{4}$ "	6"	6 $\frac{3}{4}$ "	4 $\frac{7}{8}$ "
11" Rise to 12" Run.....	6 $\frac{1}{4}$ "	5 $\frac{3}{4}$ "	6 $\frac{3}{4}$ "	4 $\frac{7}{8}$ "
12" Rise to 12" Run.....	6"	5 $\frac{3}{4}$ "	6 $\frac{3}{4}$ "	4 $\frac{7}{8}$ "
13" Rise to 12" Run.....	6"	5 $\frac{3}{4}$ "	6 $\frac{3}{4}$ "	4 $\frac{7}{8}$ "
14" Rise to 12" Run.....	6"	5 $\frac{3}{4}$ "	6 $\frac{3}{4}$ "	4 $\frac{7}{8}$ "




# DETAILS OF IMPERIAL ROMAN AND GREEK TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Deck section showing  
No. 211 ridge.




Deck section showing  
No. 211 cut-off ridge.




Deck section showing  
flashing over top of  
tiles (see note).




Hip section showing No. 102  
hip roll used with  
Roman Tiles.




Hip section showing  
Greek cover used as hip  
roll with Greek Tiles.




Section showing cover over  
concealed gutter. Pan is  
omitted (see note).




Deck section showing No. 206 ridge.




Deck section showing  
No. 211 deck mould-  
raised flange.




Section showing flashing  
under top of tiles (see note).



Section showing left gable rake, also  
flashing under side of tiles (see note).



Section showing flashing  
over top of tiles (see note).



Section showing flashing  
under  $\frac{3}{8}"$  Flat Shining  
Tiles (see note).

NOTE: Gable, flashing, flush deck and gutter treatments for Greek are the same as detailed for Roman Tiles.



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Floor Tiles

CHICAGO, 104 South Michigan Avenue


NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.


Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## FLOOR TILES


These shapes, in colors and textures originally manufactured for individual work of certain architects from their own designs, are now produced in quantities allowing their more general use. They are moderately priced.



Provence



Valencia



Renaissance

### PIECES PER SQUARE FOOT

Based on 1/8" mortar joint.



Provence, 3.86

Valencia, 4.28

\*Renaissance, squares, 1.88

\*Renaissance, hexagons, 3.76

\*Based on design showing square surrounded by hexagons.





# IMPERIAL ROOFING TILES

LUDOWICI-CELADON COMPANY

CHICAGO—104 South Michigan Avenue

NEW YORK—565 Fifth Avenue WASHINGTON—738 Fifteenth Street, N.W.

No  
only  
spe  
No  
par  
com  
No  
or  
(1) T  
(1a  
Compar  
color.  
(1b  
closed b  
(2) N  
All  
(3) F  
(3a  
doubled  
(and) ri  
and 6"  
nails.  
(3b  
(gutter)  
(4) W  
(4a  
stringers  
(4b  
1" x 2" b  
Fasten f  
angles to  
spaced t  
Not  
(5) Fl  
(5a  
wide. T  
with cle



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## SPANISH TILES


This pattern is available in a range of colors in a variety of surface textures

### SPECIFICATIONS

*Note: Notes are explanatory or advisory only and should not be included in the specifications.*

*Note: Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.*

*Note: Clauses are selective. Include or omit as they apply.*



#### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial Spanish tiles and fittings of (specify) color.

(1b) (*Hips shall be cut*) (and) valleys shall be cut and closed before burning.

#### (2) Nails

All nails for flashings and tiles shall be copper.

#### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) and ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (and) 4" over (gutter) (and) (valley) metal.

#### (4) Wood Strips

(4a) Provide 1" x 2" strips under end bands and 1" stringers of necessary height under (*hip rolls and*) ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

*Note: Include (4b) if roof base is concrete.*

#### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 4" under tiles and turn up edge  $1\frac{1}{2}$ ".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

#### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with  $1\frac{1}{2}$ " copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with  $2\frac{1}{2}$ " copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note: Include (6g) on circular roofs.*

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.


*Note: Include (6h) on high buildings.*

Details concerning any roofing problem furnished on request.

Other patterns shown in folders I-1, I-2, I-3, I-4 and I-6.



# DETAILS OF IMPERIAL SPANISH TILES



## CORRECT RAFTER LENGTHS FOR FULL LENGTH TILES

Based on 2" projection at eave of roof.

COURSE	RAFTER
1.....	11 1/4"
2.....	21 3/4"
3.....	31 3/4"
4.....	42"
5.....	52 1/4"
6.....	62 3/4"
7.....	72 3/4"
8.....	83"
9.....	93 1/4"
10.....	103 3/4"
11.....	113 1/4"


## HIP AND RIDGE STRINGER HEIGHTS

ROOF PITCH	HIP NO. 102	RIDGE NO. 206
4" Rise to 12" Run.....	5"	6 1/2"
5" Rise to 12" Run.....	4 7/8"	6 1/4"
6" Rise to 12" Run.....	4 3/4"	6"
7" Rise to 12" Run.....	4 1/2"	5 3/4"
8" Rise to 12" Run.....	4 1/4"	5 1/2"
9" Rise to 12" Run.....	4 1/8"	5 1/4"
10" Rise to 12" Run.....	4 1/4"	5 1/8"
11" Rise to 12" Run.....	4 1/8"	5 1/4"
12" Rise to 12" Run.....	4 1/4"	5"
13" Rise to 12" Run.....	4 1/8"	4 7/8"
14" Rise to 12" Run.....	4 1/4"	4 3/4"
15" Rise to 12" Run.....	4 1/8"	4 1/2"




# DETAILS OF IMPERIAL SPANISH TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Deck section showing  
flashing over top  
of tiles.




Deck section showing No. 206  
cut-off ridge and 3" x 4" scuppers  
draining deck.




Section showing flashing  
under  $\frac{3}{8}"$  Flat Shingle Tiles.




Deck section showing  
No. 206 deck  
mould-raised flange.



Deck section showing  
No. 206 ridge.




Hip section showing  
No. 102 hip roll.




Section showing end  
band over concealed gutter.



Section showing left  
gable rake and end band.



Section showing flashing  
under side of tiles.




Section showing flashing  
over top of tiles.



# DETAILS OF IMPERIAL SPANISH TILES AND FITTINGS


## APPLICATION OVER CONCRETE




Cut hip—Left.

Section showing valley flashing on concrete roof base.

Closed valley—Left.



Longitudinal section through roof.




Cross section through roof.


Application of wood strips to concrete roof base.  
Exact spacing of horizontal strips determined by shade of tiles.

## DIAGRAM OF EYEBROW DORMERS


SCALE 1/4" = 1'-0"




Front



Side



Front



Side

Eyebrow dormers must be constructed as shown above for Spanish tiles. Rafters and sheathing must show a straight line from the curved eave to the point directly above where it joins main roof and on a line with the point where center line of eyebrow meets main roof. See front elevation.

Larger or smaller effects can be secured providing vertical height and radii shown are increased or decreased proportionately.

Distance "A" should not be decreased and it must be increased when roof pitch is steeper than 12" rise in 12" run.

1089-B4344 TC



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## SHINGLE TILES


These patterns are available in a range of colors in a variety of surface textures

### SPECIFICATIONS

*Note:* Notes are explanatory or advisory only and should not be included in the specifications.

*Note:* Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.

*Note:* Clauses are selective. Include or omit as they apply.



#### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (*specify pattern*) Shingle tiles and fittings of (*specify*) color.

(1b) (*Hips*) (*and*) (*valleys*) shall be cut before burning.

#### (2) Nails

All nails for flashings and tiles shall be copper.

#### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

#### (4) Wood Strips

(4a) Provide  $\frac{3}{4}$ " x 1" cant strips at eaves and 1" stringers of necessary height under (*hip rolls and*) ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

*Note:* Include (4b) if roof base is concrete.

#### (5) Flashings

(5a) At sides of vertical surfaces, insert base flashing between each course of tiles. Lap 3" and extend 4" under tiles and at least 6" up wall.

(5b) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5c) Masonry wall shall be cap flashed and pointed.

(5d) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5e) Extend gutter metal up roof to a point higher than outer edge of gutter.

(5f) **Open Valleys**—Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5g) **Closed Valleys**—Flash between each course of tiles with 16" strips of same length as tiles.

(5h) **Rounded Valleys**—Flash between each course of tiles with curved strips of same length as tiles. Extend strips 8" beyond the curve at either side of valley.

#### (6) Laying

(6a) Lay tiles (*regular*) (*irregular*) with (*specify*) average exposure and not less than 2" head lap on the third course. Double tiles at eave. Fasten with ( $1\frac{1}{2}$ " ( $1\frac{1}{4}$ " (*specify*) copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

*Note:* Select whether regular or irregular and specify  $1\frac{1}{2}$ " nails for  $\frac{3}{8}$ " shingles;  $1\frac{1}{4}$ " nails for  $\frac{5}{8}$ " shingles; longer for thicker shingles.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement end bands in laps.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note:* Include (6g) on circular roofs.

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

*Note:* Include (6h) on high buildings.


Details concerning any roofing problem furnished on request.

Other patterns shown in folders I-2, I-3, I-4, I-5 and I-6.

PRINTED IN U.S.A.



# IMPERIAL SHINGLE TILES




PROVINCIAL	
Length.....	15 "
Width.....	7 "
Thickness.....	1 1/2 "
Average exposure.....	7" x 6 1/2 "
Average pieces per square.....	317
Average weight per square.....	1230 lbs.



BRITTANY	
Length.....	12 "
Width.....	7 "
Thickness.....	5/8 "
Average exposure.....	7" x 5 "
Average pieces per square.....	412
Average weight per square.....	1840 lbs.




# IMPERIAL SHINGLE TILES



Brittany Shingle Tiles



Mission cover ridge



Yale Memorial Tiles



Sprocket hip roll



# DETAILS OF IMPERIAL $\frac{3}{8}$ " FLAT AND $\frac{5}{8}$ " SLAB SHINGLE TILES AND FITTINGS

SCALE  $1\frac{1}{2}" = 1'-0"$


## IMPORTANT DATA

### $\frac{3}{8}$ " FLAT SHINGLE TILES


Length.....12"  
Width.....6"  
Average exposure.....6"x5"  
Average pieces per square.....480  
Average weight per square.....1225 lbs.

### $\frac{5}{8}$ " SLAB SHINGLE TILES


Length.....12"  
Width.....6 $\frac{1}{4}"$   
Average exposure.....6 $\frac{1}{4}"$ x5"  
Average pieces per square.....461  
Average weight per square.....1780 lbs.




$\frac{3}{8}$ " Flat Shingle Tile.




$\frac{5}{8}$ " Slab Shingle Tile.




Section A-A.




Section showing No. 203 ridge.




Hip section showing  
No. 111 Hip roll.



Cross section showing valley flashing  
on wood roof base. See specifications.




Elevation showing  $\frac{3}{8}"$   
Flat Shingle Tiles.



Front

SCALE  $\frac{1}{4}" = 1'-0"$  for  
eyebrow detail only.



Eave section showing gutter construction.

Eyebrow dormers must be constructed as shown above for  $\frac{5}{8}"$  Slab Shingle Tiles. Rafters and sheathing must show a straight line from the curved eave to the point directly above where it joins main roof and on a line with the point where center line of eyebrow meets main roof. See front elevation.

Larger or smaller effects can be secured providing

vertical height and radius shown are increased or decreased proportionately. Distance "A" should not be decreased and it must be increased when roof pitch is steeper than 12" rise in 12" run.

Crowd tiles at top of dormer and spread them at eave. Shorten exposure of tiles as they leave main roof until tail lines of tiles on both surfaces are aligned.



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles


CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.


Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## INTERLOCKING SHINGLE TILES



CLOSED SHINGLE

These patterns are available in a range of colors in a variety of surface textures.



ENGLISH SHINGLE

## SPECIFICATIONS

**Note:** Notes are explanatory or advisory only and should not be included in the specifications.

**Note:** Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.

**Note:** Clauses are selective. Include or omit as they apply.

### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (Closed) (English) Shingle tiles and fittings of (*specify*) color.

(1b) (*Hips*) (*and*) (*valleys*) shall be cut before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap  $2\frac{1}{2}$ " horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

### (4) Wood Strips

(4a) Provide  $\frac{3}{4}$ " x 1" cant strips at eaves.

**Note:** Include (4a) if English Shingles are specified.

(4b) Provide 1" stringers of necessary height under (*hip rolls and*) ridges.

(4c) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

**Note:** Include (4c) if roof base is concrete.

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over  $\frac{1}{4}$ ". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 5" under tiles and turn up edge  $\frac{1}{4}$ ".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with 2" copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with 2" copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with  $2\frac{1}{2}$ " copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

**Note:** Include (6g) on circular roofs.

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

**Note:** Include (6h) on high buildings.

Details concerning any roofing problem furnished on request.


Other patterns shown in folders I-1, I-3, I-4, I-5 and I-6.



# DETAILS OF IMPERIAL INTERLOCKING SHINGLE TILES

## IMPORTANT DATA

CLOSED SHINGLE	
Length.....	11 <sup>n</sup>
Width.....	8 <sup>3</sup> / <sub>4</sub> <sup>n</sup>
Average length exposure.....	8 <sup>n</sup>
Average width exposure.....	8 <sup>n</sup>
Average pieces per square.....	225
Average weight per square.....	900 lbs.
ENGLISH SHINGLE	
Length.....	13 <sup>1</sup> / <sub>4</sub> <sup>n</sup>
Width.....	8 <sup>3</sup> / <sub>4</sub> <sup>n</sup>
Average length exposure.....	10 <sup>1</sup> / <sub>8</sub> <sup>n</sup>
Average width exposure.....	7 <sup>1</sup> / <sub>8</sub> <sup>n</sup>
Average pieces per square.....	182
Average weight per square.....	900 lbs.



## CORRECT RAFTER LENGTHS FOR FULL LENGTH TILES

Based on 2" projection at eave of roof.

COURSE	CLOSED SINGLE	ENGLISH SINGLE
1	9"	11 $\frac{1}{2}$ "
2	17"	21 $\frac{1}{2}$ "
3	25"	31 $\frac{1}{2}$ "
4	33"	41 $\frac{1}{2}$ "
5	41"	51 $\frac{1}{2}$ "
6	49"	61 $\frac{1}{2}$ "
7	57"	72"
8	65"	82 $\frac{1}{2}$ "
9	73"	92 $\frac{1}{2}$ "
10	81"	102 $\frac{1}{2}$ "
11	89"	112 $\frac{1}{2}$ "


## HIP AND RIDGE STRINGER HEIGHTS

Roof Pitch	CLOSED SHINGLE		ENGLISH SHINGLE	
	HP No. 118	RIDGE No. 211	HP No. 120	RIDGE No. 211
4" Rise to 12" Run.	27" 31"	31"	31"	3"
5" Rise to 12" Run.	28" 31"	29"	31"	3"
6" Rise to 12" Run.	29" 31"	28"	31"	2 1/2"
7" Rise to 12" Run.	30" 31"	26"	31"	2 1/2"
8" Rise to 12" Run.	31" 31"	25"	31"	2"
9" Rise to 12" Run.	32" 31"	24"	31"	1 3/4"
10" Rise to 12" Run.	33" 31"	23"	31"	1 1/2"
11" Rise to 12" Run.	34" 31"	22"	31"	1 1/8"
12" Rise to 12" Run.	35" 31"	21"	31"	1"
13" Rise to 12" Run.	36" 31"	20"	31"	7/8"
14" Rise to 12" Run.	37" 31"	19"	31"	3/4"




# DETAILS OF IMPERIAL INTERLOCKING SHINGLE TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Deck section showing  
No. 211 ridge.




Deck section showing  
No. 211 deck  
mould-raised flange.




Deck section showing  
No. 211 cut-off  
ridge.




Deck section showing  
flashing over top  
of tiles.




Section showing flashing  
under  $\frac{3}{8}"$  Flat Shingle Tiles.



Section showing flashing  
under side of tiles.




Section showing gutter  
construction for English  
Shingle Tiles.




Hip section showing No. 118  
hip roll used with Closed  
Shingle Tiles.




Section showing right gable  
rake and end band.




Section showing sunken gutter treatment.  
Note: When English Shingle Tiles are used, under eaves are  
omitted and distance below gutter is  $11\frac{1}{4}"$ .



Section showing flashing  
over top of tiles.



Cut hip—Left.




Cut valley—Right.




# DETAILS OF IMPERIAL INTERLOCKING SHINGLE TILES AND FITTINGS

APPLICATION OVER CONCRETE


SCALE  $1\frac{1}{2}" = 1'-0"$



Section showing valley flashing on concrete roof base.



Longitudinal section through roof.




Cross section through roof.


Application of wood strips to concrete roof base.  
Exact spacing of horizontal strips determined by shade of tiles.

## DIAGRAM OF EYEBROW DORMERS


SCALE  $\frac{1}{4}" = 1'-0"$




Front



Front



Side



Side

Eyebrow dormers must be constructed as shown above for Closed Shingle Tiles. Rafters and sheathing must show a straight line from the curved eave to the point directly above where it joins main roof and on a line with the point where center line of eyebrow meets main roof. See front elevation.

Larger or smaller effects can be secured providing

vertical height and radii shown are increased or decreased proportionately. Distance "A" should not be decreased and it must be increased when roof pitch is steeper than 12" rise in 12" run.

NOTE: For English Shingle tiles, eyebrow width and distance "A" must be increased 2'-0". The height remains the same.



# LUDOWICI-CELADON COMPANY

Makers of *IMPERIAL Roofing Tiles*

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## FRENCH TILES

This pattern is available in a range of colors

## SPECIFICATIONS

*Note:* Notes are explanatory or advisory only and should not be included in the specifications.

*Note:* Words in italics enclosed within parentheses are selective to suit particular condition. Include or omit as required.

*Note:* Clauses are selective. Include or omit as they apply.



### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's *Imperial French* tiles and fittings of (*specify*) color.

(1b) (*Hips*) (*and*) (*valleys*) shall be cut before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap 2½" horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

### (4) Wood Strips

(4a) Provide 1½"x2" cant strips at eaves and 1" stringers of necessary height under (*hip rolls* *and*) ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit tiles.

*Note:* Include (4b) if roof base is concrete.

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over ½". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 5" under tiles and turn up edge ½".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles to straight lines, parallel and at right angles to eaves, lapped 3". Fasten with 2½" copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) Leave opening of 6" or more across valleys.

(6c) Cement gable rakes to field tiles and fasten with 2" copper nails.

(6d) Cement hip rolls in laps and fasten with 2" copper nails.

(6e) Cement ridges in laps and fasten with 2½" copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

*Note:* Include (6g) on circular roofs.

(6h) Cement all tiles in laps, using 40 lbs. of elastic cement per square.

(6i) Copper clamp shall be placed in side lock of each tile at point directly above head of tile below. Nail clamp to roof base.

*Note:* Include either (6h) or (6i) on high buildings.


Details concerning any roofing problem furnished on request.  
Other patterns shown in folders I-1, I-2, I-4, I-5 and I-6.



## DETAILS OF IMPERIAL FRENCH TILES

IMPORTANT DATA

Length.....	16 $\frac{1}{4}$ "
Width.....	9"
Average length exposure.....	13 $\frac{3}{8}$ "
Average width exposure.....	8 $\frac{5}{8}$ "
Average pieces per square.....	133
Average weight per square.....	935 lbs.



### CORRECT RAFTER LENGTHS FOR FULL LENGTH TILES

Based on 2" projection at eave of roof.

COURSE	RAFTER
1.....	14"
2.....	27 $\frac{3}{8}$ "
3.....	40 $\frac{3}{8}$ "
4.....	54 $\frac{1}{8}$ "
5.....	67 $\frac{1}{2}$ "
6.....	80 $\frac{7}{8}$ "
7.....	94 $\frac{1}{4}$ "
8.....	107 $\frac{5}{8}$ "
9.....	121"
10.....	134 $\frac{3}{8}$ "


### HIP AND RIDGE STRINGER HEIGHTS

ROOF PITCH	HIP NO. 102	RIDGE NO. 206
4" Rise to 12" Run.....	4 $\frac{3}{4}$ "	5 $\frac{1}{4}$ "
5" Rise to 12" Run.....	4 $\frac{1}{2}$ "	5"
6" Rise to 12" Run.....	4 $\frac{1}{4}$ "	4 $\frac{3}{4}$ "
7" Rise to 12" Run.....	4 $\frac{1}{2}$ "	4 $\frac{1}{2}$ "
8" Rise to 12" Run.....	4 $\frac{1}{4}$ "	4 $\frac{1}{4}$ "
9" Rise to 12" Run.....	4 $\frac{1}{2}$ "	4"
10" Rise to 12" Run.....	4 $\frac{1}{4}$ "	3 $\frac{3}{4}$ "
11" Rise to 12" Run.....	4 $\frac{1}{2}$ "	3 $\frac{1}{2}$ "
12" Rise to 12" Run.....	4 $\frac{1}{4}$ "	3 $\frac{1}{4}$ "
13" Rise to 12" Run.....	4 $\frac{1}{2}$ "	3"
14" Rise to 12" Run.....	4 $\frac{1}{4}$ "	2 $\frac{7}{8}$ "
15" Rise to 12" Run.....	4 $\frac{1}{2}$ "	2 $\frac{5}{8}$ "




# DETAILS OF IMPERIAL FRENCH TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Cut hip—Left.




Section showing flashing under side of tiles.



Deck section showing No. 206 deck mould-raised flange.




Section showing valley flashing on concrete roof base.



Section showing flashing under  $\frac{3}{8}"$  Flat Shingle Tiles.


Cut valley—Right.




Section showing flashing over top of tiles.




Section showing right gable rake.




Longitudinal section through roof. Application of wood strips to concrete roof base. Exact spacing of horizontal strips determined by shade of tiles.




Cross section through roof.




Section showing sunken gutter treatment.



Hip section showing No. 102 hip roll.



Deck section showing No. 206 ridge.



Deck section showing No. 206 cut-off ridge.



(1)

Comp  
fittin  
(  
and c

(2)

(3)

doub  
(and)  
and t  
nails  
(gutta

(4)

ers (k  
1" x 2"  
Faste  
angle  
strip

(5)

wide  
with



# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Roofing Tiles

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## MISSION TILES


These patterns are available in a range of colors in a variety of surface textures

## SPECIFICATIONS

**Note:** Notes are explanatory or advisory only and should not be included in the specifications.

**Note:** Words in *italics* enclosed within parentheses are selective to suit particular condition. Include or omit as required.

**Note:** Clauses are selective. Include or omit as they apply.



### (1) Tiles

(1a) Cover roofs so indicated with Ludowici-Celadon Company's Imperial (*specify pattern*) Mission Tiles and fittings of (*specify*) color.

(1b) Covers shall be used as (*hip roll and*) ridge.

(1c) (*Hips shall be cut*) (*and*) valleys shall be cut and closed before burning.

### (2) Nails

All nails for flashings and tiles shall be copper.

### (3) Felt

(3a) Lay asphalt felt weighing 30 lbs. per square, doubled on (*low pitches*) (*rough surfaces*) (*hips*) (*valleys*) (*and*) ridges. Lay parallel to eaves. Lap 2½" horizontally and 6" vertically. Fasten with large-headed galvanized nails.

(3b) Extend felt (6" up vertical walls) (*and*) 4" over (*gutter*) (*and*) (*valley*) metal.

### (4) Wood Strips

(4a) Provide 1" strips of necessary height under covers (*hip rolls*) and ridges.

(4b) Embed parallel with the pitch on 20" centers 1" x 2" beveled wood strips flush with surface of concrete. Fasten felt with lath nailed over these strips. At right angles to embedded strips, over lath, install 1" x 2" strips spaced to suit pan tiles.

**Note:** Include (4b) if roof base is concrete.

### (5) Flashings

(5a) Line valleys with 16 oz. copper at least 20" wide. Turn edge over ¼". Lap joints at least 4". Fasten with cleats. Do not solder.

(5b) At sides of vertical surfaces, extend base flashing at least 6" up wall, 4" under tiles and turn up edge 2".

(5c) At fronts, extend flashing at least 3" up wall and 4" over tiles.

(5d) Masonry wall shall be cap flashed and pointed.

(5e) Where tile and metal roofs intersect, extend metal up tile roof 12" or more.

(5f) Extend gutter metal up roof to a point higher than outer edge of gutter.

### (6) Laying

(6a) Lay tiles (*regular*) (*irregular*) exposure with not less than 3" lap. Fasten with 2" copper nails. Fasten tiles overlapping sheet metal with copper wire and elastic cement.

(6b) **Irregular Effect**—Lay pans at actual exposure. Vary exposures of covers to avoid horizontal and diagonal lines using 10% additional covers.

(6c) Leave opening of 6" or more across valleys.

(6d) Cement gable rakes to field tiles and fasten with 2½" copper nails.

(6e) Cement (*hip rolls*) (*and*) (*ridges*) in laps and fasten with 2½" copper nails.

(6f) Where tiles join hip stringers make waterproof with elastic cement.

(6g) Cement small pieces of graduated tiles solidly with elastic cement.

**Note:** Include (6g) on circular roofs.

(6h) Cement all tiles in laps, using 30 lbs. of elastic cement per square.

**Note:** Include (6h) on high buildings.


Details concerning any roofing problem furnished on request.

Other patterns shown in folders I-1, I-2, I-3, I-5 and I-6.




# DETAILS OF IMPERIAL STRAIGHT BARREL MISSION TILES AND FITTINGS


LUDOWICI-CELADON COMPANY



Section showing split cover gable rake, also flashing under side of tiles.



Section showing cover over concealed gutter.  
Pan is omitted.




## IMPORTANT DATA

Length.....	14 1/4"	.....	18"
Width center to center of covers.....	11 1/2"	.....	11 1/2"
Average length exposure.....	11 1/4"	.....	15"
Average pieces per square.....	224	.....	170
Average weight per square.....	1250 lbs.	.....	1250 lbs.

SCALE 1 1/2" = 1'-0"



# DETAILS OF IMPERIAL SMALL TAPERED MISSION TILES AND FITTINGS




Section showing cover over concealed gutter. Pan is omitted.

## IMPORTANT DATA


SMALL TAPERED PANS AND COVERS	
Length	14 1/4"
Width center to center of covers	9 1/2"
Average length exposure	11 1/4"
Average pieces per square	270
Average weight per square	1380 lbs.

SMALL TAPERED COVERS AND 14 1/4" STRAIGHT BARREL PANS	
Length, pan	14 1/4"
Length, cover	14 1/4"
Width center to center of covers	10"
Average length exposure, pans	11 1/4"
Average length exposure, covers	11 1/4"
Average pieces per square, pans	128
Average pieces per square, covers	128
Average weight per square	1350 lbs.


SCALE 1 1/2" = 1'-0"




Small Tapered pans and covers.



Section showing Small Tapered pans and covers, also split cover gable rake.




Section showing Small Tapered covers with 14 1/4" Straight Barrel pans, also split cover gable rake.



Small Tapered covers and Straight Barrel pans.



# DETAILS OF IMPERIAL ROMAN AND GREEK TILES



## IMPORTANT DATA

	ROMAN	GREEK
Length.....	12 <sup>3</sup> / <sub>4</sub> "	12 <sup>3</sup> / <sub>4</sub> "
Width center to center of covers.....	12"	12"
Average length exposure.....	10"	10"
Average pieces per square.....	240	240
Average weight per square.....	1100 lbs.	1250 lbs.

## CORRECT RAFTER LENGTHS FOR FULL LENGTH ROMAN OR GREEK TILES

Based on 2" projection at eave of roof.

COURSE	RAFTER
1.....	10 <sup>3</sup> / <sub>4</sub> "
2.....	20 <sup>1</sup> / <sub>4</sub> "
3.....	30 <sup>1</sup> / <sub>4</sub> "
4.....	40 <sup>1</sup> / <sub>4</sub> "
5.....	50 <sup>1</sup> / <sub>4</sub> "
6.....	60 <sup>1</sup> / <sub>4</sub> "
7.....	70 <sup>1</sup> / <sub>4</sub> "
8.....	80 <sup>1</sup> / <sub>4</sub> "
9.....	90 <sup>1</sup> / <sub>4</sub> "
10.....	100 <sup>1</sup> / <sub>4</sub> "
11.....	110 <sup>1</sup> / <sub>4</sub> "


## HIP AND RIDGE STRINGER HEIGHTS

Roof Pitch	Hip No. 102	Ridge No. 206	Hip-Cover	Greek Ridge No. 211
4" Rise to 12" Run.....	6 <sup>3</sup> / <sub>4</sub> "	7 <sup>1</sup> / <sub>4</sub> "	7"	6"
5" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	7"	7"	5 <sup>3</sup> / <sub>4</sub> "
6" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	6 <sup>3</sup> / <sub>4</sub> "	7"	5 <sup>1</sup> / <sub>4</sub> "
7" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	7"	5 <sup>1</sup> / <sub>4</sub> "
8" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	6 <sup>3</sup> / <sub>4</sub> "	5 <sup>1</sup> / <sub>4</sub> "
9" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	5"
10" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	6"	6 <sup>1</sup> / <sub>4</sub> "	4 <sup>7</sup> / <sub>8</sub> "
11" Rise to 12" Run.....	6 <sup>1</sup> / <sub>4</sub> "	5 <sup>3</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	4 <sup>3</sup> / <sub>8</sub> "
12" Rise to 12" Run.....	6"	5 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	4 <sup>1</sup> / <sub>8</sub> "
13" Rise to 12" Run.....	6"	5 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	4 <sup>1</sup> / <sub>8</sub> "
14" Rise to 12" Run.....	6"	5 <sup>1</sup> / <sub>4</sub> "	6 <sup>1</sup> / <sub>4</sub> "	4 <sup>1</sup> / <sub>8</sub> "




# DETAILS OF IMPERIAL ROMAN AND GREEK TILES AND FITTINGS


SCALE  $1\frac{1}{2}" = 1'-0"$




Deck section showing  
No. 211 ridge.




Deck section showing  
No. 211 cut-off ridge.




Deck section showing  
flashing over top of  
tiles (see note).




Hip section showing No. 102  
hip roll used with  
Roman Tiles.




Hip section showing  
Greek cover used as hip  
roll with Greek Tiles.




Section showing cover over  
concealed gutter. Pan is  
omitted (see note).




Deck section showing No. 206 ridge.




Section showing left gable rake, also  
flashing under side of tiles (see note).




Deck section showing  
No. 211 deck mould-  
raised flange.



Section showing flashing  
over top of tiles (see note).



Deck section showing  
No. 206 deck mould-  
raised flange.



Section showing flash-  
ing under  $\frac{3}{4}$  Flat Shin-  
gle Tiles (see note).

NOTE: Gable, flashing, flush deck and gutter  
treatments for Greek are the same as detailed  
for Roman Tiles.







# LUDOWICI-CELADON COMPANY

*Makers of IMPERIAL Roofing Tiles*


CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

*Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS*

## TILE SLABS



In addition to shale red colors, tile slabs are manufactured in a range of browns and fire-flashed shades. A complete line of tile slab fittings is available.

### NUMBER OF PIECES PER SQUARE


Mortar Joint	6"x6"x1"	6"x9"x1"	9"x9"x1"
$\frac{1}{8}$ "	384	258	173
$\frac{1}{4}$ "	369	250	168
$\frac{3}{8}$ "	355	241	164
$\frac{1}{2}$ "	341	234	160



6"x9"x1"



6"x6"x1"



## GARDEN WALK EDGING

Made in red, fire-flashed and black. Placed in the ground along walks or driveways it makes an interesting and practical edging for lawns or flower borders.


## TILE FLAGGING

Made in a variety of colors. The texture suggests that of old stone flagging.

Size approximately 9"x12"x1 $\frac{1}{4}$ ".









# LUDOWICI-CELADON COMPANY

Makers of IMPERIAL Chimney Pots

CHICAGO, 104 South Michigan Avenue

NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.

Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS

## CHIMNEY POTS

Chimney pots are made in various textures and colors especially adapted to use with our weathered effect tiles. They are also available in glazed colors for the modern treatment.




C.P. 200



C.P. 500, 510 and 520



C.P. 600, 610, 620, 630,  
640, 650 and 660



C.P. 400, 410 and 420



C.P. 300, 310 and 320

### SCHEDULE OF SIZES

NUMBER	FLUE	BASE	HEIGHT
C.P. 200.....	7½"x7½"	13"x13"	15"
C.P. 300.....	8" Dia.	14"	18"
C.P. 310.....	12" Dia.	18"	21"
C.P. 320.....	15" Dia.	21"	25"
C.P. 400.....	8" Dia.	14½"	25"
C.P. 410.....	12" Dia.	18½"	29"
C.P. 420.....	15" Dia.	21"	32"
C.P. 500.....	8" Dia.	14"	15"
C.P. 510.....	12" Dia.	18"	18"
C.P. 520.....	15" Dia.	21"	22"
C.P. 600.....	10" Dia.	13"	15"
C.P. 610.....	12" Dia.	15"	18"
C.P. 620.....	15" Dia.	18"	20"
C.P. 630.....	18" Dia.	21½"	23"
C.P. 640.....	23" Dia.	26"	30"
*C.P. 650.....	8"x12"	11"x15"	20"
*C.P. 660.....	12"x17"	15"x20"	30"

\*Elliptical







# LUDOWICI-CELADON COMPANY

*Makers of IMPERIAL Floor Tiles*

CHICAGO, 104 South Michigan Avenue


NEW YORK, 565 Fifth Avenue

WASHINGTON, 738 Fifteenth Street, N. W.


*Factories located at NEW LEXINGTON, OHIO—COFFEYVILLE, KANSAS—PERU, KANSAS*

## FLOOR TILES



These shapes, in colors and textures originally manufactured for individual work of certain architects from their own designs, are now produced in quantities allowing their more general use. They are moderately priced.



Provence



Valencia



Renaissance

### PIECES PER SQUARE FOOT

Based on 1/4" mortar joint.



Provence, 3.86

Valencia, 4.28

\*Renaissance, squares, 1.88

\*Renaissance, hexagons, 3.76

\*Based on design showing square surrounded by hexagons.





NEW  
CLP

Li  
Li  
Li  
Li  
Li

Fr  
Obi  
clay  
our  
pro  
non  
rich  
ing

L  
with  
rug  
hou  
roo  
o  
Col  
det  
han  
C  
Mis  
and  
var  
sur  
V  
as  
to  
of



# LUDOWICI-CELADON COMPANY

Makers of "Ludowici" Roofing Tiles

NEW YORK, N. Y.  
CLEVELAND, OHIO

104 South Michigan Avenue  
CHICAGO, ILL.

WASHINGTON, D. C.  
OKLAHOMA CITY, OKLA.

**AUTHENTIC IN EVERY DETAIL, LUDOWICI TILES FAITHFULLY REPRODUCE THE EFFECT OF OLD WORLD ROOFS**

## Products

LUDOWICI ROOFING TILES.  
LUDOWICI CHIMNEY POTS.  
LUDOWICI GARDEN WALK EDGING.  
LUDOWICI TILE SLABS.  
LUDOWICI TILE FLAGGING.

## Manufacture

From the Ludowici clay pits of Ohio and Kansas come the finest clays obtainable. These clays, under our special manufacturing methods, produce hard-burned roofing tiles of non-reflective texture, whose soft, rich colors are obtained in the burning process—hence are permanent.

## Texture

Ludowici Shingle Tile reproduce with historic accuracy the crude, rugged charm of the French farmhouse and the English countryside roofs, and give the required feeling of weight your design demands. The Colonial shingles reproduce in every detail the texture and color of old, hand-split wood shingles.

Closed Shingle, English Shingle, Mission, Spanish, Roman, Italian, and Greek tiles are also produced in various textures, including weathered surface effects.

Variations in great number, both as to color and texture can be had to meet the individual requirements of architectural design and taste.



## Colors

Ludowici Shingle tiles are produced in a wide variety of colors, ranging from light tans and buffs through varying reds, browns and purples, to greys, brownish blacks and dark weathered greens.

Ludowici Spanish, Mission, French, English Shingle, Closed Shingle, Roman, Italian, and Greek tiles are offered in natural reds and fireflashed shades, or glazes of most any color.

## Permanence and Durability

A roof of Ludowici tiles will last as long as the building it covers. Once laid, it provides a permanently beautiful, weathertight and fireproof roof, with distinct insulating qualities; assures lifelong protection without the expense of painting or repairs.

## Reasonable in Cost

A Ludowici tile roof is moderate in price, and can be installed without any special framing for the substructure.

## Service to Architects

We invite you to write or call your nearest Ludowici representative for samples of tile, complete specifications, and for aid on any roofing problem you may have. Estimates promptly furnished from architects' complete plans and specifications.

Provincial Shingle



Size 7 1/4" x 15" x 1/2"  
Exposure 7 1/4" x 6 1/4"  
295 pieces per sq.  
Average weight per square, 1300 lbs.

Brittany Shingle



Size 7" x 12" x 3/4"  
Exposure 7" x 5"  
412 pieces per sq.  
Average weight per square, 1650 lbs.

Antique Shingle



Size 7" x 12" x 3/4"  
Exposure 7" x 5"  
412 pieces per sq.  
Average weight per square, 1525 lbs.

Colonial Shingle



Size 7" x 15" x 3/4"  
Exposure 7" x 6 1/4"  
317 pieces per sq.  
Average weight per square, 1600 lbs.

ROOFING-TILES, CLAY, IMPERIAL  
LUDOWICI-CELADON COMPANY  
A. I. A. FILE NUMBER 12-21



# LUDOWICI-CELADON COMPANY

Norman Shingle

Size 7" x 12" x 5/8"  
Exposure 7" x 5"  
410 pieces per sq.  
Average weight per square, 1360 lbs.




Yale Memorial Tile

Standard Sizes:  
Lengths 12", 14", 16"  
Widths 6", 7", 8".  
Thicknesses 3/8",  
3/4", 1". Exposure  
and weight varies  
according to the  
size of tile used.




Spanish

Size 13 1/4" x 9 3/4"  
Exposure 10 1/4" x 8 1/4"  
171 pieces per sq.  
Average weight per square, 850 lbs.



Straight Barrel Mission

Lengths, 18", 14 1/4"  
Exposures 15" x 11 1/2"  
and 11 1/4" x 11 1/2".  
18" length 166 pieces  
per sq. Wt. 1200  
lbs. 14 1/4" length  
224 pieces per sq.  
Weight, 1225 lbs.



Cubana Tapered Mission

Size 18" x 11 1/4"  
Exposure 15" x 11 1/4"  
170 pieces per sq.  
Average weight per square, 1300 lbs.  
18" Straight Barrel  
Mission Pans.



18-in. Tapered Mission

Size 18" x 10"  
Exposure 15" x 10"  
192 pieces per sq.  
Average weight per square, 1300 lbs.  
18" Straight Barrel  
Mission Pans.



Roman



Made in two sizes: 10" x 12" exposure, 240 pieces per sq.; 15" x 19" exposure, 102 pieces per sq. Wt., small size, 1150 lbs.; large size, 1400 lbs.

Greek



Made in two sizes: 10" x 12" exposure, 240 pieces per sq.; 15" x 19" exposure, 102 pieces per sq. Wt., small size, 1285 lbs.; large size, 1450 lbs.

Italian



Size of tile width 11 1/4" x length 12 1/4". Exposure 9 1/4" x 11 1/4", 276 pieces per square. Average weight per square is 1350 pounds.

## LUDOWICI CHIMNEY POTS FOR USE WITH WEATHERED-EFFECT TILES

Chimney pots are made to fit standard flue linings. They are available in various textures and colors, with glazed or unglazed finish.



C.P. 200



C.P. 300, 310, 320

### STANDARD STOCK SIZES

NUMBER	FLUE	BASE	HEIGHT
C.P. 200	7 1/2" x 7 1/2"	13" x 13"	15"
C.P. 300	8" Diam.	14"	18"
C.P. 310	12" Diam.	18"	21"
C.P. 320	15" Diam.	21"	25"
C.P. 400	8" Diam.	14 1/2"	25"
C.P. 410	12" Diam.	18 1/2"	29"
C.P. 420	15" Diam.	21"	32"
C.P. 500	8" Diam.	14"	15"
C.P. 510	12" Diam.	18"	18"
C.P. 520	15" Diam.	21"	22"
C.P. 600	10" Diam.	13"	15"
C.P. 610	12" Diam.	15"	18"
C.P. 620	15" Diam.	18"	20"
C.P. 630	18" Diam.	21 1/2"	23"
C.P. 640	23" Diam.	26"	30"
*C.P. 650	8" x 12"	11" x 15"	20"
*C.P. 660	12" x 17"	15" x 20"	30"

\*Elliptical.



C.P. 400, 410, 420



C.P. 500, 510, 520



C.P. 600, 610, 620, 630, 640, 650, 660



ROOFING-TILES, CLAY, IMPERIAL  
LUDOWICI-CELADON COMPANY

A. I. A. FILE NUMBER

12-1

520

0, 620,  
0, 660

S. A.



